



ADMINISTRATION | ENGINEERING
501 E LEMON STREET W-ADMN/ENG
LAKELAND, FL 33801-5079
863.834.8316 | Fax 863.834.6274
www.lakelandgov.net/water

“Treating Your Water Seriously”

City of Lakeland, Water Operations As-Built/Record Drawing Checklist

In addition to the listed requirements of design plans, as-built or record drawings must be dated, signed and sealed on 24-inch by 36-inch and submitted to the City of Lakeland for approval by the Water Operations Group. All design and construction must be in conformance with requirements as identified in the City of Lakeland, Water Operations Policies, Standards and Specifications for Subdivisions and Commercial Developments.

All As-built/Record drawings submitted must show/state:

- _____ Materials/Change of materials
- _____ Dimensions of water main to edge of pavement
- _____ Dimensions of service valves/stubs to edge of pavement and propertyline
- _____ Dimensions of restrained joints, fittings and dead ends
- _____ Locations of all sample points
- _____ Locations of all fittings, valves, tees
- _____ Indicate on drawings any portions of design not constructed on As-Built as “proposed”
- _____ Signed and sealed by Engineer of Record
- _____ Depth to top of water main